



STRUCTURAL AND CIVIL ENGINEERS

Fax Number 654 392 Job No W 8165
Job Name 249 Madras st Shrochval report
To Robin Schulz of Schulz Knight
From John Harc
Time 10-40 Date 31 1 90
Re:
Please see over a draft copy of our report, for your information & convent
Regards John Hare.

Page 1 of | Page:

Holmes Consulting Group Limited, 61 Cambridge Terrace, P.O. Box 701, Christchurch, New Zealand. Telephone: (03) 663-366. Facsimile: (03) 792-169.

W8165

ALAN REAY CONSULTANTS LIMITED

147 KILMORE STREET BOX 25-028, VICTORIA ST CHRISTCHURCH 1 Telephone: 660-434 Fax No: (03) 793-981

ALAN M. REAY B.E.(Hons.), Ph.D. M.N.Z.I.E. Registered Engineer Structural Consultant

File 3608

2 February 1990

PECEIVED

JMH

7 FEB 1990

HOLMES CONSULTING
GROUP LIMITED
CHRISTCHURCH

HOLMES CONSULTING
CHRISTCHURCH

Mr Grant Wilkinson Holmes Consulting Group PO Box 701 CHRISTCHURCH

Dear Sir

RE: 249 MADRAS STREET

Further to our discussions by telephone this morning, we confirm that the scope of the possible non-compliance referred to in your report on the building is the connections between the walls on gridlines D and D/E, as shown on the attached sketch SK1 from levels 2 to 6 inclusive (Level 1 being the ground floor carpark).


The proposed remedial work, if required, would consist of a total of two ties per floor, tying the walls to the floor diaphragm.

The agreed maximum tie load is 300 kN per tie. We understand that this load would be reduced on lower floors in accordance with the "Parts and Portions" section of NZS 4203:1984.

Please contact this office today if your understanding of the situation is not as outlined above.

Yours faithfully

G.N. Banks



F

AL N REAY CONSULTANTS LIMITED

147 KILMORE STREET BOX 25-038 VICTORIA ST CHRISTCHURCH I Telgolione: 080-434 Fax No: (03) 793-981

ALAN M. REAY
R.F. (Huns.), Ph.D.
M.N.Z.) h
Registered Engineer
Strugtural Consultable

File 3600.

FACSIMILIE TRANSMISSION

- HJH

DATE: 2/02/90
10: HOLHES CONSLICTING GROUP
ATTENTION: CRANT WILLIAMSON
CITY: CHRISTEHURCH
RECEIVERS FAX NO: (03)792-169
FROM: GEOFF BANKS
MFSSAGE:
RE: 249 HADRAS ST
III. I I the and state as discussed.

Regards, Geoff

ALAN REAY CONSULTANTS LIMITED

147 KILMORE STREET BOX 25-028, VICTORIA ST CHRISTCHURCH 1 Talephone: 880-434 Fax No: (03) 793-981

ALAN M. RSAY D.E.(Honn.), Ph.D. M.N.Z.I.E. Registered Engineer Structural Consultant

File 3608

2 February 1990

Mr Grant Wilkinson Holmes Consulting Group PO Box 701 CHRISTCHURCH

Dear Sir

RE: 249 MADRAS STREET

Further to our discussions by telephone this morning, we confirm that the scope of the possible non-compliance referred to in your report on the building is the connections between the walls on gridlines D and D/E, as shown on the attached sketch SK1 from levels 2 to 6 inclusive (Level 1 being the ground floor carpark).


The proposed remedial work, if required, would consist of a total of two ties per floor, tying the walls to the floor diaphragm.

The agreed maximum tie load is 300 kN per tie. We understand that this load would be reduced on lower floors in accordance with the "Parts and Portions" section of NZS 4203:1984.

Please contact this office today if your understanding of the situation is not as outlined above.

Yours faithfully

G.N. Banks





STRUCTURAL REPORT

OFFICE BUILDING 249 MADRAS STREET

Prepared for

CANTERBURY REGIONAL COUNCIL

by Holmes Consulting Group, Christchurch

in association with Buddle Findlay Limited and Schulz Knight Consultants Limited

January 1990

Holmes Consulting Group Limited, 61 Cambridge Terrace, P.O. Box 701, Christchurch, New Zealand. Telephone: (03) 663-366. Facsimile: (03) 792-169.

CONTENTS

1.0	Introduction.
2.0	People involved with construction of this building.
3.0	Conclusions.
4.0	Summary of Investigation.
5.0	Structural Design Aspects.
6.0	Condition Report.

W8165REP

JANUARY 1990

1.0

INTRODUCTION

Holmes Consulting Group Limited were engaged on 24th January 1990 by Buddle Findlay Limited and Schulz Knight Consultants Limited to prepare a structural report on the office development located at 249 Madras Street. The building was completed during 1987 and is currently untenanted.

2.0 PEOPLE INVOLVED WITH CONSTRUCTION OF THIS BUILDING

Developer Prime West Corporation

Contractor Williams Construction Limited

Architect Alun Wilkie Architects

Structural Engineer Alan M. Reay Consulting Engineer

Mechanical Consultant

Electrical Consultant

Soils Consultant Soils & Foundations Limited

3.0

CONCLUSIONS

Due to the limited time available for the report, our review has been limited to a brief inspection of the building and documents, and approximate calculations. No materials testing has been undertaken, and inspection has been limited to such areas as were readily accessible. Given these qualifications, our conclusions are as follows:-

- 1. The building is in a condition appropriate to its age and the contractor-as-developer form of construction.
- 2. The layout and design of the building is quite simple and straight forward and generally complies with current design loading and materials codes.
- 3. A vital area of non-compliance with current design codes, seen in the documents, is in the tying of the floors to some of the shear walls. This item is under review with the original consultants, but if confirmed will require potentially expensive remedial work. However, this cost is a matter for discussion between the current owner and their consultants.
- 4. Apart from ongoing maintenance costs which should be minor, no major costs are anticipated in association with the structure, subject to 3. above.

4.0

SUMMARY OF INVESTIGATION

A full set of Architectural drawings, and some structural drawings were made available from Alun Wilkie Architects.

In addition, we were able to view the full design, documentation, Soils Investigation and complete set of drawings at the office of Alan M. Reay Consulting Engineer, on 26 January 1990. The original design engineer was unavailable for comment, having since left the company, but Mr Geoff Banks was available for comment on aspects of the design.

We have spoken to Mr Bryan Bluck, Buildings Control Manager at the Christchurch City Council, to discuss any concerns relating to the building permit and construction process.

An inspection was made on 30th January 1990. Levels 1 and 4 were unavailable for inspection, but the remaining floors were taken as representative. Access was gained to the Lift Machine room, Cooling tower and onto the roof.

5.0

DESCRIPTION

1.	No. storeys and occupancy:	5 storeys office (floor to floor height typically 2600 clear) and ground floor parking.
2.	Gross Floor dimensions:	approx. 31m x 22.5 m.
3.	Foundation type:	Shallow strip footings and foundations pads, with large foundation walls under structural shear walls.
4.	Suspended Floors:	200mm overall insitu concrete on metal tray, supported by precast concrete beams on insitu columns on a 7.5m x 7.0m grid generally.
5.	Roof construction:	Lightweight metal cladding on steel purlins and beams, supported on insitu concrete columns.
6.	Floor Design liveloads:	2.5 kPa typically (minimum load level required by NZS 4203: 1984).
7.	Lateral load resistance:	This is via a reinforced concrete coupled shear wall on the south face of the building, and a system of reinforced concrete walls around the service core on the north face of the building.
8.	Exterior Cladding:	400 deep x 100 mm precast spandrel panels with glazing between, or on West elevations 140 mm blockwall to level 4 with metal cladding above perforated for windows.
9.	Exterior maintenance:	No allowance for a Building Maintenance Unit has been made. Access for external cleaning is through windows. With opening windows restricted to a single pair approx. 1.0 m wide per 7.5 m bay, this is limited, although the spandrel panels are sufficiently wide for a person to stand safely.

STRUCTURAL DESIGN ASPECTS

6.1 Foundations

6.0

From the soils investigation report prepared by Soils and Foundations Limited, we note that settlement was highlighted as a potential problem, particularly in the north-east corner of the site, causing differential settlement concerns. The pad and strip foundations were sized using the recommendations of the report on maximum allowable stresses. However the recommendations of the report on a maximum pressure to limit settlement appear not to have been followed. It is not known whether any ground improvement work was undertaken to compensate for this.

However, inspection of the site revealed no sign of any significant settlement. Given that most settlement occurs within a relatively short time of construction, this should not become a significant problem in the future.

6.1 Gravity Structure

From our perusal of the drawings, and our investigation of the building, it appears the gravity structure is sound and complies in all respects with the appropriate design loading and materials codes. Furthermore it was noted in the documentation that although only a 2.5 kPa standard office live load was called for, the floor will withstand a live load of up to 3.4 kPa. This would be subject to further confirmation.

6.3 Lateral load resistance

Resistance to lateral loads is via reinforced concrete shear walls.

The shear walls themselves appear to have been generally well designed to the requirements of the correct design loading and materials codes. The building was apparently analysed using a 3 dimensional computer analysis programme checked by a static hand analysis.

An area of concern however has been discovered in the connections of the structural floor diaphragm to the shear walls. While this is not a concern on the coupled shear wall to the south of the building, connections to the walls at the North face of the building are tenuous, due to penetrations for services, lift shafts and the stairs, as detailed on the drawings.

The result of this would be that in the event of an earthquake, the building would effectively separate from the shear walls well before the shear walls themselves reach their full design strength.

Discussion has continued on this matter with Mr Geoff Banks of Alan Reay Consulting Engineer, and it currently appears that there may have been some provision made for this during construction. However, no documentation apparently exists, so it would only be safe to assume that this aspect fails to comply with current design codes.

6.4 Roof

Due to its light weight nature, the roof is prone to deflections, particularly in wind. A brief check shows that the deflections should be within allowable limits, as prescribed in the current codes. However, in our experience, movement may be quite perceptible and disconcerting for the occupants and in extreme wind, may cause damage to ceiling tiles.

Furthermore, it was noted on inspection that the internal butynol lined gutters at roof level have only one downpipe with no provision for an overflow. This is a potential problem in the event of a blockage to a downpipe.

6.5 Fire Escape

On the south face there is a steel cantilevering fire escape. This is currently in good condition but it should be noted that this type of construction is prone to corrosion and should be the subject of an on-going maintenance programme.

7.0 CONDITION REPORT

As expected for a building of this age, the structure appears generally in sound condition. Although mainly concealed by carpets and ceilings, those parts of the structure accessible to view reveal no signs of distress.

Standards of workmanship are adequate although finishes and details appear to have been given the minimum of effort. This is commensurate with the type of development and the time at which it was built.

There has been some water damage to ceiling tiles at level 5 adjacent to the wall between the lifts and the stairwell. This is probably due to a failed flashing.

During the inspection it was noted that there is evidence of cracking on the end of the spandrel panels on either side of the fire escape. The finish in these areas is different to the rest of the panels. It appears that the crack has formed at the interface between the spandrel panel itself and the beam supporting it. In the worst instance this crack may propagate above floor level and cause waterproofing problems.

The roof is mainly in good condition, although several panels of the Trimdek roofing have been dented quite badly. Furthermore, there is evidence of some ponding in the gutters which appear to have minimal fall. (refer to section 6.4 for further comment).

The Trimdek cladding should be subject to a performance guarantee. This would have to be checked with the current owners.



HOLMES CONSULTING GROUP STRUCTURAL AND CIVIL ENGINEERS Offices in Christchurch, Wellington, New Plymouth, Auckland.

MEMO	
JOB NAME 249 Madas St.	
JOB NAME 249 Madras St. JOB NO WBIGS	01/02/90
To: Warren & Mahoney	
Attn: Kerry Mason	
Kerry	
The second secon	/ 1/
Martin Charles advises that the c	art do
(as per attached sheets) will be	Works
(as per attached sheets) will be	apprex
\$14,000 + GST.	
Do de Me else from	us as this
Do you need anything else from 306?	
<i>Joo</i> .	
Regards	
7-9417-12	
15-	
Grant Williamon	
COPIES TO	15.



OB NAME 249 Madras St. OB NO W8/65 Comedial Works Steel angle required at 5 heels. 2 per level at 5 heels. 4 heels have responded tile ceilings in gard. I heal has plasterboard to paint ceiling and answer all weels have carpet.	MEMO	
Steel angle required: 2 per level at 5 levels. 4 levels have responded tile ceilings in grad. 1 level hap plasterboard + paint ceilings arrowe all levels have carpet.	JOB NAME 249 Madras St.	
Steel angle required: 2 per level at 5 levels. 4 levels have responded tile ceilings in grad. 1 level hap plasterboard + paint ceilings arrowe all levels have carpet.	JOB NO WORL	DATE /02/90
Steel angle registed. 2 per level at 5 levels. 4 levels have suspended tile ceilings in good. 1 level has plasterboard + paint ceilings assure all levels have carpet.	77 0,63	4/64/5
Steel angle registed. 2 per level at 5 levels. 4 levels have suspended tile ceilings in good. 1 level has plasterboard + paint ceilings assure all levels have carpet.		
Steel angle registed. 2 per level at 5 levels. 4 levels have suspended tile ceilings in good. 1 level has plasterboard + paint ceilings assure all levels have carpet.	Remedial Works	
4 levels have suspended tile ceilings in good. I level has plasterboard + paint ceiling accorded all levels have carpet.		
4 levels have suspended tile ceilings in good. I level has plasterboard + paint ceiling accorded all levels have carpet.	Steel angle regerred	
4 levels have suspended tile ceilings in good. I level has plasterboard + paint ceiling accorded all levels have carpet.	1 per level at 5 kuplr.	
assure all levels have carpet.		
assure all levels have carpet.		1
assure all levels have carpet.	- 4 /evels have suspended tile ceilings	in grad.
assure all levels have carpet.	I level has plasterboard + paint	ceil.
	-assure all levels have carely	
		,
	,	



STRUCTURAL AND CIVIL ENGINEERS


Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

PAGE S/C-01 DATE 31/1/90.



· Detail typical to levels 1 to 5.

STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.


CALCULATIONS

JOB NAME

JOB No

CALCS BY

PAGE SC-02



- · Mark out & drill boke before cutting or drilling steel. Locate steel in wall prior to Ddrilling boles.
- · Holes in wall to be of drilled using percussive robors drill. Epoxy bors using Exporters & of equivalent.



STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.


CALCULATIONS

JOB NAME

JOB No

CALCS BY

PAGES 603 DATE



- * Prior to drilling holes locate HIZ-ZOD bars top steel in slab. Confirm detail with engineer if any clash occurs.
- · Mark out and drill holes through slab prior to cotting steel.
- angle to orderside of slab, and seal around gaps between thood ribs.
- · Growing ap using SIKA 212 or similar



STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

P A G E D A T E

Renedial work to N/S mills at tiff shelf. Tit/Cit = 300 LW Eith may. a wall 300 the : practically only deep enough to develope DIZ. in Auf 2 300 = 1429 _ 2 m & : region N = 1429/13 = 12-6 a Similar area of steel regit under slab. with angle tre less are of holes of leg - At 2 300/250 = 1200 -- 2. = 0 Kh, 120 well : less 2 rows holes => 200 x 200 x 10 m.s.

HOLMES CONSULTING GROUP STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch,	Wellington,	New	Plymouth,	Auckland.	

COPIES TO

MEMO JOB NAME W 81 65 JOB NO	DATEZ9/20.
Bryan Block 2-15	
- Clad legal definitions	of Luce
dubient en quality of com of Fire escape. - some relling v. bad. time will have constru	in logis. Than. Faults
- Terrible devator - vehicle dearance.	

STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.

MEMO

JOB NAME ZAM Madras St.

DATE 76 1 90

@ Alan Reay.

by piezby l= 2.5 hla. -possibly capacity

-corld clec

Cd = . 1 as

anchisis

Shahic EV= 3300 hw OTN= 47254 Lw-

T= T= 1.06 sec :

x.712 : better.

Dyramic archysis personel

2 [

PD = 1493 P. = 182 461 35 215 5 234 2073 7 1898 351

541

STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.

15 #		B 81	-
M	L-	N/I	
IAI		IVI	- U

JOB NAME JOB No

DATE

Wall 3 OTrade 1646 hw- Vede = 349 cf calc Pap = 405 Pap = 496.

Wall 4 M= 8662 hw~?

Wall 5 - nax Mil= 16278 ch calc 15873.

Diaphaga calcs performed p S 51,57

T x - 6 for wall @ edge = IOO hw - xx

-@ line 1 & A only -no drag bars for ofter walks

STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.

MEMO

JOB NAME JOB No

DATE

Foundations

soils Insestination by S&F 18 Jue 86.

rec shallow poted bothings or piles. - reduced pressure NE and Por ribbish.

bearing stresses range 100 - 200 hla allocable.

- osed 200 regid stresses a 50-125 to timet settlement.

- Pads appear to be @ = 180 h/c Par 42

Designed bears to SM-1-6

to not live 1 - used overstrey?

- seems of

- 606 @

HOLMES CONSULTING GROUP STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.

周周		图 周	0
IMI	-	IV/I	()
IAI	R.,	IWI	u

JOB NAME

JOB No

DATE

Rock steel

178×79 RSJ @ 7-00 spa @7300cms!

COPIES TO

STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME ZAG Madras of JOB NO W8165 CALCS BY

PAGE DATE ZS/A 90

APPROX SEISMIC AWALYSIS.

Floors all hypical 200 Hibord on precast beans 400×5500.a Core chear wells son 400 g columns.

=> Afloor= 30.9 × 23.5 = 726 ~2 efforx. lbeans = 74.5 m 400 x 550(353)

+ 60.5 ~ 260 x 550 (350)

Challs = 26n @ 350 Confled.

oblines = 20 + latingt wall l= 93 -.

: WE = 726 x 4-5 + 74.5 x , 35 x , 4 x 25 400 x 550 scans + 60.5 x -96 x.35 x 75 960 × 550 ~ 300 malls + 76 x - 3x 3 - 29 x 75 + 4x,4x 3.24 x 25 900 malls + 20 xT1 x.43/4 x 25 x 2.69 00000 claddin + ,3x 93 x 3.24

P= 5057 WN

h= 2.6 A Level 7 = 7 × 4.5 For alls Po = 600 hw L=7.4 A Couch 8 = 11.5 x 4.5 + Someralls Po. 700km. Higheyhover

take live load - 2.5 lale Applical - P/3 = 605 hu + 5-0 hla @ hul 7,8 : 1/3 = 53 hw 7

= 86 hw 8

STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

PAGE DATE

= Lave & WE = 5 (5057 + 605) + (600 + 53) + (700 + 86) = 29750 hu

Cd= CRSM = 175 x1-0 x1.0 x0.8 = 011 or .8 Par couled mall : V base = 2975 LN.

= @ worst, . 6 V/wall for E/W action N/s action. · 5V

W WL F Fh Lul 8 786 20.20 16663 7 653 18.80 12276 6 5662 16.20 91724 5 12-96 73380 4 9.72 55035 3456 163 120 225% 897 14531 815 9305 538 5229 359 6.48 36690 2326 3.24 18345 179 580 2974 37683. 21750

h CFG = 10.22 m.

-> Lool @ diaphrogn. @ hul 6 Sp=1-0 : Cp-1x = 0.3 Cp= K Krez R Cp-nx = 0.76 × 5/6 ×1.0× 6.3 = , 19.

STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

P A G E D A T E

= 0.6 Vstorey to vall - V= .19x.6x 5662

= 645 hw.

This lock nust go via small section

of slab = 2600 long x 200 thich

Wi = 645/2x26 = 1.24 m/z.

The section over reaction of met

To Vi = 2x645/2x226

= 292 m/z

Ny/2 = .59 m/z

Ays = 1554 mJ.

We DITS- 70 crs.

OR, as say oversheight = 2.0 -ax

3 V: = 2x645/2x26 = 2.48 m/c.

2 DN Nc = .2/Fiz = 1.18 m/c

4 M/S 2 867 -2/ eFy=300

4 D12-130

4 D12-400+ mesh?

STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

P A G E D A T E

Description | 1-5 x1316 = 1971 hm.

20 1/2-16 Pe Ag = .62 onla.

20 1/2-16

Other ralls all get HIZs-200 1) vo = ex prode = 9629 : prode = 9629/6 x 20.12 = 798 h... : Viall = 1196 how : Vi=1.92 mls. @ .6 Je/s = .704 mls - Au/s = 890 ~ - Lave 1131 ~ 2/2 oils

creek on him ing.

STRUCTURAL AND CIVIL ENGINEERS


Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

PAGE DATE



STRUCTURAL AND CIVIL ENGINEERS


Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

P A G E D A T E



STRUCTURAL AND CIVIL ENGINEER


Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

PAGE DATE



== 1232 = 65, 215, 3135, 3285, 226 @ 475,875,1275,1675,2075,2475,2875



STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

P A G E D A T E

Total capacity of malls E & Mi = .9 (5474×2+12432+ 7451) = 27748LW_. ch calculated 6/dg OTM = 37000 hw. in have 75 % e full Vshah - allowing for Dynamic analysis reduction Go , a Ushat + over exhibition = 83 % of a Ushat Torsions to be resisted on offer malle. @ 2 Mil= (2×7000 + 9629+ 15873) = 39502 ~ 8 = 35,502/27748 = 1.42 ~ as expected - allowing for reduced Usbat base. and ther Vehil = 2500/-6,20.12 : Vila 1.42 x 2070 = 2939 LL. alternately, on 2, - Mcd= 15873 hwn inpliquing of Vi code 2 15873 6×20.12 = 1314 hm. will W= 1.5 @ 6 storeys

STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

PAGE DATE

Recheel diaphragen.

GO V = 300 house holy scaled value. Vetoriax. 517 \$.60

- WILL 8 012-400

: available Ve e 300 Ma.

DUSIE 271 hw.

(is if 2 layers 664 rest are included - 2 APVSI : 385 LN.

Require - with dw = 2.5 -0 Vi & = 750

: che=25 ml= - De= ·25/c= 1-0 ml.

of U = 750/2×2-6×12 = 1-8 MP -. AVS 7 -8×200/500 = 533 ~2/-. ⇒ DIZs+ 664×2 = 493 -2/2 - Cose

but have a problem where OIZs stop

before litting behood.

after director . all ralls. : Take Ni= 30% 6 x 2.5 = 1250 hu. => reguin bersion steel for this.

STRUCTURAL AND CIVIL ENGINEERS Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

P A G E D A T E

- As 3 1250 (1.5 x 300 = 362 m/s.

- As 3 1250 (1.5 x 300 = 362 m/s.

- Thirdwally

-nall Live DE for calcs Vcode=349hw

=> Vil= z-5 × 349= 875 hw.

i vsig distr calculated,

inplies Vstragil-ax = 268hw.

- Woll again At 2 263/300 = 876 -2 - Lave no steel. - ranke 2-HIZ T= 95LN.

Similarly, wall @ C

-calc Mil= 16278 (from DH calcis)

- Vid= 16278/37683 × 897

= 387 LN.

- Lave ~10-DIZ - Vs= 339 Lw -0.L.

Walls between.

Similar loads but I wall takes end of
beau - appears o.L. Other cute slab, but no
steel shown. - possibly 2-412?

STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

PAGE DATE

- Line 1 (South mall) - Probably oil

E-W 29.

Line A+ (North wall)

E-Wez.

~ marginal

C (West boulet wall)

Line C-D (East nall toilet (West shair) N/S - probably oh.

D (Lift sheft/Shair well) W/S Live

no steel shows - or not much

D/E (East Lift shaft)

- No steel ?

Entire shear core slightly discious.

STRUCTURAL AND CIVIL ENGINEER

Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS


JOB NAME

JOB No

CALCS BY

P A G E D A T E

On extrar shear cove



Cutting as shown. ~ get 4000 H12-200 - Vs= 410×4×565 = 927 L.N + 664 wesh over 11.5 ~. Vs=11.5 × 269 × 275 = 851 Lw - plenty already.

STRUCTURAL AND CIVIL ENGINEERS

Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

P A G E D A T E

Check rost h= 21 Hq - san 20 m.

 $V = 40, S_1 = 1.0, S_2 = .9$ $V_S = 36 - /s : q = .794 U.fa.$

= @ Gri = ±0.3, Cpe = -1-0

-on 7.5 x 7 grid - l= 7000, hib widt - 7500

-> Ww= 7.7% hm/-.

178,88 RSJ : Sw= 16.2 -- = -0023 L @ full continuit

: enderfan - = 33.7 m = .0048 L - high.

: would expect some problems with tiles.

-> on 5-yr mind - drop q to . 541 hda.

: Work 5 27 hours = 11.1 - mid.

: endspan = 23-0 m

= -0033 L -still a title lingh.

assume strengt o, - drech. eps=-35 hla

Moto = 39 hw.

ef Mxx == 28.9 hw => weign approx



Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

P A G E D A T E

= end = fans - 4.75 -.

: wliz=+16.7 hwn W.70-w=-5.89

or inter-al wliz=+24.1hw.

- over lo-1400

-12.6 over l-5000.

cf Uprs end = -18.0 over le=(con-just ok)

int = -26.0 + 13
od @ capacity = 78.9 hwm. fr.



Offices in Christchurch, Wellington, New Plymouth, Auckland.

CALCULATIONS

JOB NAME JOB No

CALCS BY

PAGE 25/0/90

Ala May 660 734.

9,11,14,15,16,17,19, 25,26,30,3132, 33,36

Eone in any time