



HOLMES CONSULTING GROUP
STRUCTURAL AND CIVIL ENGINEERS

STRUCTURAL REPORT

**OFFICE BUILDING
249 MADRAS STREET**

Prepared for

CANTERBURY REGIONAL COUNCIL

by Holmes Consulting Group, Christchurch

**in association with Buddle Findlay Limited
and Schulz Knight Consultants Limited**

January 1990

Holmes Consulting Group Limited,
61 Cambridge Terrace,
P.O. Box 701,
Christchurch, New Zealand.
Telephone: (03) 663-366.
Facsimile: (03) 792-169.

Offices in Christchurch, Wellington, New Plymouth, Auckland.

CONTENTS

- 1.0 Introduction.
- 2.0 People involved with construction of this building.
- 3.0 Conclusions.
- 4.0 Summary of Investigation.
- 5.0 Structural Design Aspects.
- 6.0 Condition Report.

W8165REP

JANUARY 1990

1.0

INTRODUCTION

Holmes Consulting Group Limited were engaged on 24th January 1990 by Buddle Findlay Limited and Schulz Knight Consultants Limited to prepare a structural report on the office development located at 249 Madras Street. The building was completed during 1987 and is currently untenanted.

2.0 PEOPLE INVOLVED WITH CONSTRUCTION OF THIS BUILDING

Developer	Prime West Corporation
Contractor	Williams Construction Limited
Architect	Alun Wilkie Architects
Structural Engineer	Alan M. Reay Consulting Engineer
Mechanical Consultant	
Electrical Consultant	
Soils Consultant	Soils & Foundations Limited

3.0

CONCLUSIONS

Due to the limited time available for the report, our review has been limited to a brief inspection of the building and documents, and approximate calculations. No materials testing has been undertaken, and inspection has been limited to such areas as were readily accessible. Given these qualifications, our conclusions are as follows:-

1. The building is in a condition appropriate to its age and the contractor-as-developer form of construction.
2. The layout and design of the building is quite simple and straight forward and generally complies with current design loading and materials codes.
3. A vital area of non-compliance with current design codes, seen in the documents, is in the tying of the floors to some of the shear walls. This item is under review with the original consultants, but if confirmed will require potentially expensive remedial work. However, this cost is a matter for discussion between the current owner and their consultants.
4. Apart from ongoing maintenance costs which should be minor, no major costs are anticipated in association with the structure, subject to 3. above.

4.0

SUMMARY OF INVESTIGATION

A full set of Architectural drawings, and some structural drawings were made available from Alun Wilkie Architects.

In addition, we were able to view the full design, documentation, Soils Investigation and complete set of drawings at the office of Alan M. Reay Consulting Engineer, on 26 January 1990. The original design engineer was unavailable for comment, having since left the company, but Mr Geoff Banks was available for comment on aspects of the design.

We have spoken to Mr Bryan Bluck, Buildings Control Manager at the Christchurch City Council, to discuss any concerns relating to the building permit and construction process.

An inspection was made on 30th January 1990. Levels 1 and 4 were unavailable for inspection, but the remaining floors were taken as representative. Access was gained to the Lift Machine room, Cooling tower and onto the roof.

5.0

DESCRIPTION

1. No. storeys and occupancy: 5 storeys office (floor to floor height typically 2600 clear) and ground floor parking.
2. Gross Floor dimensions: approx. 31m x 22.5 m.
3. Foundation type: Shallow strip footings and foundations pads, with large foundation walls under structural shear walls.
4. Suspended Floors: 200mm overall insitu concrete on metal tray, supported by precast concrete beams on insitu columns on a 7.5m x 7.0m grid generally.
5. Roof construction: Lightweight metal cladding on steel purlins and beams, supported on insitu concrete columns.
6. Floor Design liveloads: 2.5 kPa typically (minimum load level required by NZS 4203 : 1984).
7. Lateral load resistance: This is via a reinforced concrete coupled shear wall on the south face of the building, and a system of reinforced concrete walls around the service core on the north face of the building.
8. Exterior Cladding: 400 deep x 100 mm precast spandrel panels with glazing between, or on West elevations 140 mm blockwall to level 4 with metal cladding above perforated for windows.
9. Exterior maintenance: No allowance for a Building Maintenance Unit has been made. Access for external cleaning is through windows. With opening windows restricted to a single pair approx. 1.0 m wide per 7.5 m bay, this is limited, although the spandrel panels are sufficiently wide for a person to stand safely.

6.0

STRUCTURAL DESIGN ASPECTS6.1 Foundations

From the soils investigation report prepared by Soils and Foundations Limited, we note that settlement was highlighted as a potential problem, particularly in the north-east corner of the site, causing differential settlement concerns. The pad and strip foundations were sized using the recommendations of the report on maximum allowable stresses. However the recommendations of the report on a maximum pressure to limit settlement appear not to have been followed. It is not known whether any ground improvement work was undertaken to compensate for this.

However, inspection of the site revealed no sign of any significant settlement. Given that most settlement occurs within a relatively short time of construction, this should not become a significant problem in the future.

6.1 Gravity Structure

From our perusal of the drawings, and our investigation of the building, it appears the gravity structure is sound and complies in all respects with the appropriate design loading and materials codes. Furthermore it was noted in the documentation that although only a 2.5 kPa standard office live load was called for, the floor will withstand a live load of up to 3.4 kPa. This would be subject to further confirmation.

6.3 Lateral load resistance

Resistance to lateral loads is via reinforced concrete shear walls.

The shear walls themselves appear to have been generally well designed to the requirements of the correct design loading and materials codes. The building was apparently analysed using a 3 dimensional computer analysis programme checked by a static hand analysis.

An area of concern however has been discovered in the connections of the structural floor diaphragm to the shear walls. While this is not a concern on the coupled shear wall to the south of the building, connections to the walls at the North face of the building are tenuous, due to penetrations for services, lift shafts and the stairs, as detailed on the drawings.

The result of this would be that in the event of an earthquake, the building would effectively separate from the shear walls well before the shear walls themselves reach their full design strength.

Discussion has continued on this matter with Mr Geoff Banks of Alan Reay Consulting Engineer , and it currently appears that there may have been some provision made for this during construction. However, no documentation apparently exists, so it would only be safe to assume that this aspect fails to comply with current design codes.

6.4 Roof

Due to its light weight nature, the roof is prone to deflections, particularly in wind. A brief check shows that the deflections should be within allowable limits, as prescribed in the current codes. However, in our experience, movement may be quite perceptible and disconcerting for the occupants and in extreme wind, may cause damage to ceiling tiles.

Furthermore, it was noted on inspection that the internal butynol lined gutters at roof level have only one downpipe with no provision for an overflow. This is a potential problem in the event of a blockage to a downpipe.

6.5 Fire Escape

On the south face there is a steel cantilevering fire escape. This is currently in good condition but it should be noted that this type of construction is prone to corrosion and should be the subject of an on-going maintenance programme.

7.0 CONDITION REPORT

As expected for a building of this age, the structure appears generally in sound condition. Although mainly concealed by carpets and ceilings, those parts of the structure accessible to view reveal no signs of distress.

Standards of workmanship are adequate although finishes and details appear to have been given the minimum of effort. This is commensurate with the type of development and the time at which it was built.

There has been some water damage to ceiling tiles at level 5 adjacent to the wall between the lifts and the stairwell. This is probably due to a failed flashing.

During the inspection it was noted that there is evidence of cracking on the end of the spandrel panels on either side of the fire escape. The finish in these areas is different to the rest of the panels. It appears that the crack has formed at the interface between the spandrel panel itself and the beam supporting it. In the worst instance this crack may propagate above floor level and cause waterproofing problems.

The roof is mainly in good condition, although several panels of the Trimdek roofing have been dented quite badly. Furthermore, there is evidence of some ponding in the gutters which appear to have minimal fall. (refer to section 6.4 for further comment).

The Trimdek cladding should be subject to a performance guarantee. This would have to be checked with the current owners.

(F)

ALAN REAY CONSULTANTS LIMITED

ALAN M. REAY
B.E.(Hons.), Ph.D.
M.N.Z.I.E.
Registered Engineer
Structural Consultant

147 KILMORE STREET
BOX 25-028, VICTORIA ST
CHRISTCHURCH 1
Telephone: 660-434
Fax No: (03) 793-981

File 3608.FACSIMILIE TRANSMISSION

DATE: 2/02/90
TO: HELMES CONSULTING GROUP
ATTENTION: GRANT WILKINSON
CITY: CHRISTCHURCH
RECEIVERS FAX NO: (03) 792-169
FROM: GEOFF BANKS
MESSAGE:
RE: 249 MADRAS ST

Attached letter and sketch as discussed.

Regards, Geoff

PLEASE CONTACT IMMEDIATELY IF 3 PAGES (INCLUDING THIS) ARE NOT RECEIVED.

ALAN REAY CONSULTANTS LIMITED

ALAN M. REAY
B.E.(Hons.), Ph.D.
M.N.Z.I.E.
Registered Engineer
Structural Consultant

147 KILMORE STREET
BOX 25-028, VICTORIA ST
CHRISTCHURCH 1
Telephone: 660-434
Fax No: (03) 793-981

File 3608

2 February 1990

Mr Grant Wilkinson
Holmes Consulting Group
PO Box 701
CHRISTCHURCH

Dear Sir

RE: 249 MADRAS STREET


Further to our discussions by telephone this morning, we confirm that the scope of the possible non-compliance referred to in your report on the building is the connections between the walls on gridlines D and D/E, as shown on the attached sketch SK1 from levels 2 to 6 inclusive (Level 1 being the ground floor carpark).

The proposed remedial work, if required, would consist of a total of two ties per floor, tying the walls to the floor diaphragm.

The agreed maximum tie load is 300 kN per tie. We understand that this load would be reduced on lower floors in accordance with the "Parts and Portions" section of NZS 4203:1984.

Please contact this office today if your understanding of the situation is not as outlined above.


Yours faithfully



G.N. Banks

Sketch 3608/SK1

2/02/90



3808

14/02/90.

② Jim Hare, HERT 9:00 am.

1. Agreed loads	300	L5
	240	L4
	184	L3, 2, 1.

2. Continued the only system at - possible pre-tension via nuts

3. Continued reduced corrosion if it may be at (could compensate at (2 if necessary). Will continue to work proceeds

CB

CALCULATIONSALAN M. REAY
CONSULTING ENGINEER
CHRISTCHURCH

244 MADRAS ST - DIAPHRAGM CHECK

PAGE 1
SECT
FILE 3608
DATE 29/01/90

- Building has 5 suspended floors and a lightweight roof.
- Check floor diaphragm connection to wall on line S, line D and line E.

1. Geometry

refer sketch attached for layout.

2. Loads • refer SSS of previous calc

- 2.1 Previous Calc
- checked line 1 & 5 walls only (level 5)
 - 60% load to each
 - used fixed static design shear at 50 kN (storey), no overstrength.

2.2 Check Port & Props

• storey weight = 6217 kN @ level 5.

• $C_p^{\max} = 0.3$ for multi-storey• $C_p = \alpha K_a Z R C_p$

$$\alpha = \frac{h_{eg}}{h_u}$$

$$h_{eg} = \frac{W_{ah}}{\sum W_u} = \frac{316105}{31766} = 9.95 \text{ m}$$

$$h_u = 20.50$$

$$\Rightarrow \alpha = \frac{9.95}{20.50} = 0.49$$


for storey:

$$K_a = \frac{h_{u2}}{h_{eg}} = \frac{16.20}{9.95} = 1.63$$

$$Z = 5/6 \quad \text{zone B}$$

$$R = 1.0$$

$$C_p = 0.3$$



CALCULATIONSALAN M. REAY
CONSULTING ENGINEER
CHRISTCHURCHPAGE 2
SECT
FILE 3600
DATE 29/6/20

$$\Rightarrow C_p = (0.49)(1.63)(5/6)(1.0)(0.3) = 0.20$$

$$\Rightarrow \text{storey shear} = (0.20) 6217$$

$$= \boxed{1241 \text{ kN}}$$

2.3 Storey Shear Distribution2.3.1 Y-direction eq

• distribute according to storey shear distⁿ at ground:

$$\frac{\text{wall (4)}}{(\text{case 3})} \quad \frac{1925}{330} (1241) = 0.58 \times 1241$$

$$= \underline{\underline{724 \text{ kN}}}$$

2.3.2 X-direction eq

$$\frac{\text{wall (3)}}{(\text{case 1})} \quad \frac{613}{3298} (1241) = \underline{\underline{231 \text{ kN}}}$$

$$\frac{\text{wall (9)}}{(\text{case 1})} \quad \frac{741}{3298} (1241) = \underline{\underline{279 \text{ kN}}}$$

CALCULATIONSALAN M. REAY
CONSULTING ENGINEER
CHRISTCHURCHPAGE 3
SECT
FILE 3609
DATE 29/01/903 Design Connections - Reinforcement3.1 Wall ④ design $V_u = 724 \text{ kN}$ over 2.65 m lengthshear friction to wall (roughened surface $\geq 5 \text{ mm}$)

$$A_v = \frac{724 \times 10^3}{2.65 (0.85 \times 1.4) 275} = 835 \text{ mm}^2/\text{m}$$

• have D12 @ 400 + 2 layers 664 mesh.

$$A_{s \text{ reqd}} = \frac{113}{0.4} + 2 \left[\frac{186 \times 485}{275} \right] = 939 \text{ mm}^2/\text{m} > 835 \Rightarrow \text{OK}$$

diaphragm

$$V_f = \frac{724 \times 10^3}{0.85 \times 150 \times 2650} = 2.14 \text{ MPa}$$

$$V_c = 0.2 \sqrt{f'_c} = 1.00 \text{ MPa}$$

$$V_f = 1.14 \text{ MPa}$$

$$A_v = \frac{1.14 \times 150 \times 10^3}{485} = 353 \text{ mm}^2/\text{m}$$

• have 2 layers 664 mesh = $2 \times 186 = 372 \text{ mm}^2/\text{m} \Rightarrow \text{OK}$ wall line 5 connection OK3.2 Wall ③

$$\text{tension tie to slab: need } A_t = \frac{231 \times 10^3}{0.9 \times 380} = 675 \text{ mm}^2$$

CALCULATIONSALAN M. REAY
CONSULTING ENGINEER
CHRISTCHURCH

PAGE

4

SECT

FILE

3608

DATE

1/02/90

4. Design Connections - Bolted.• For walls 349, $T_u = 279$ kN max.

try fabricated angle:

bolts: (in shear) - use $\phi_s = 3.3$ for EQ

$$\text{Chemset M20; } U_n = \frac{85.7}{3.3} = 26.0 \text{ kN.}$$

$$\text{Inbolt T20; } U_n = \frac{85.3}{3.3} = 25.8.$$

} require.

$$\Rightarrow N^e_{req'd} = \frac{279}{26.0} = 11 \quad \text{— high!}$$

$$\text{try M24 Chemset, } U_n = \frac{127.6}{3.3} = 38.7$$

$$\Rightarrow N^e_{req'd} = \frac{279}{38.7} = 7.2 \quad \text{; say 7. (b3 3.2)}$$

7-M24 Chemset Anchors

$$\text{steel area: } A_{st} = \frac{279}{0.250} = 1116 \text{ mm}^2.$$

$$\Rightarrow \underline{150 \times 12 \text{ mm 2 Plat}}$$

CALCULATIONS

ALAN M. REAY
CONSULTING ENGINEER
CHRISTCHURCH


PAGE

5

SECT

FILE

DATE



steel: 50 kg @ \$2/kg = \$100 steel

bolts: max 15 @ \$10 = \$150

labour

\$340.

\$500 (incl.)

CALCULATIONSALAN M. REAY
CONSULTING ENGINEER
CHRISTCHURCHPAGE 5A
SECT
FILE 3608
DATE 10/10/915 Design Connection - Tie Systems.

- design tie load for walls ③ + ④ from 2.3.2 is 279 kN maximum, for both + Portals.
- agreed max. design load with HWRT is 300 kN
⇒ use this as a maximum at levels 5 (of analysis model) and reduce for lower levels.

5.1 Loads

$$\text{at level 5: } \alpha k_x = (0.49)(1.63) = 0.80$$

Uden.
300 kN

$$\text{at level 4: } \alpha k_x = (0.49) \left(\frac{12.96}{9.95} \right) = 0.64 \Rightarrow$$

240 kN

$$\text{at level 3: } \alpha k_x = (0.49)(1.00) = 0.49 \Rightarrow$$

184 kN

$$\text{at level 2: } \alpha k_x = \text{" " " "}$$

184 kN

$$\text{at level 1: } \alpha k_x = \text{" " " "}$$

184 kN

5.2 Compression Transfer

- check whether slab/wall junction can handle compression transfer without reinforcement:

$$f_{pc} = \frac{300 \times 10^3}{300 \times 200} = 5.0 \text{ MPa}$$

conservative

$$\text{allowable } F_c = (0.85 \times 0.70) 250 = 14.9 \text{ MPa}$$

⇒ compression easily ok.

CALCULATIONS

ALAN REAY CONSULTANTS LTD
Consulting Engineers
Christchurch

PAGE 7A.
SECT.
FILE 3608
DATE 10/10/91.

5.3 Tension Tie

5.3.1 Wall N° 9.

- use angle bolted to wall & floor as previous detail
- 2-H2 ties located in the wall end at level 2.
- capacity of these 2 bars is:

$$T_u = 0.9 \cdot (113 \times 380) \cdot 2 = 77 \text{ kN.}$$

- check if level 2 & 1 can be transferred to other walls (see section 6), \Rightarrow design bracket for the following loads:

			M20	M24 Chorus
Level 5:	$300 - 77$	$= 223 \text{ kN.}$	9	6
Level 4:	$240 - 77$	$= 163 \text{ kN.}$	6 ⁶⁵	5
Level 3:	$184 - 77$	$= 107 \text{ kN.}$	4	3

- try using M24 Chorus Incha. to wall.

- ultimate shear load = 127.6 kN.

- load case 0.8 E

- use ϕ s of 4-0 for working loads, \Rightarrow for loads above, use $0.8 \times 4.0 = 3.2$.

$$\therefore U_{M24} = \frac{127.6}{3.2} = 40 \text{ kN.}$$

\Rightarrow N° bolts shown above \rightarrow

- recommended spacing = 160 mm.

\Rightarrow detail bracket as shown over.

CALCULATIONS

ALAN REAY CONSULTANTS LTD
Consulting Engineers
Christchurch

PAGE 8A.
SECT.
FILE 3608
DATE 10/10/91

• use M20 anchors to floor

$$V_{H20} = \frac{85.7}{3.2} = 27 \text{ kN.} \quad (\text{see 7A for N's})$$

CALCULATIONS

ALAN REAY CONSULTANTS LTD
Consulting Engineers
Christchurch

PAGE 9A
SECT
FILE 3608
DATE 10/10/91

S-3.2 Wall N° 3

as wall 9, except only 1-H2bar per level located

⇒ design loads as follows:

			H20	H29
level 5:	300-38	= 262 kN	10	7
level 4:	240-38	= 202 kN	8	5
level 3:	184-38	= 146 kN	6	4

⇒ bolt numbers as noted:
(Chamset)

→

→

CALCULATIONSALAN REAY CONSULTANTS LTD
Consulting Engineers
ChristchurchPAGE 121.
SECT
FILE 3608.
DATE 10/10/91.6 Shear Transfer, Levels 1 and 2

• check whether loads in diaphragms at these levels can be transferred to walls ⑤ and ⑦

• design shears for diaphragm design are as follows:
 \downarrow max shear \swarrow reduction per height

$$\text{level 2: } 1241 (0.44) = 608 \text{ kN}$$

$$\text{level 1: } 1241 (0.44) = 608 \text{ kN}$$

• from page 512 of calcs, previous static distⁿ of story shears was as follows: (x direction)
(at load through C.H.)

	⑤ ← 39% (237)	52% (315)	ie 33% increase
	⑦ ← 22% (134)	29% (172)	ie 33% increase
100% (608) →	⑨ ← 22% (134)	13% (77)	
	③ ← 7% (103)	6% (38)	
	distribution (loads)	proposed (loads)	

• strength of connection to ③ is a min of 38 kN.
 ⑨ 77 kN.

⇒ proposed revised distribution above.

CALCULATIONS

ALAN REAY CONSULTANTS LTD
Consulting Engineers
Christchurch

PAGE 13A
SECT.
FILE 3608
DATE 10/10/91

Check the effect of this increase on wall
Flexural and Shear Design:

Wall N^o 5: ref p 347 of code

code values: applied shear
at level 2: $V_{code} = 870 - 762 = 108 \text{ kN}$ max 33%
" " 1: $= 675 - 870 = -195 \text{ kN}$ 144 kN
-259 kN

\Rightarrow max $V_{code} = 762 - 144 = 906 \text{ kN}$ at level 1 \rightarrow 2.

flexure

and max $M_{base} = 4267 + 36(69) - 64(37) = 4279 \text{ kNm}$
i.e. 0.2% increase

negligible

\Rightarrow no increase required in flexural capacity

shear: ref p 347 s.

	C	T
at level 2: new $V_s =$	4.34	2.54
V_E	2.07	0.55
V_S	<u>2.27</u>	1.99
A_v	1791 mm ² /m	

have H16 @ 250 c/c - 608 mm²/m 90%
but note wall length 38% longer than
assumed in code \Rightarrow OK

shear

CALCULATIONS

ALAN REAY CONSULTANTS LTD
Consulting Engineers
Christchurch

PAGE 14A
SECT.
FILE 3608
DATE 10/10/91

Wall No 7 : refer to p 348 of code

code section :

info not available on section above ground floor.

however :

Stress : max. possible moment increase

is $(178-134)(6.9+3.7) = 466 \text{ kNm}$.

on design Mode = 3972 kNm, i.e. 12% over.

but detail for ductility \Rightarrow OK.

(likely bar strength margin = $\frac{430}{380} = 1.13$) \Rightarrow OK.

shear : governed by overstrength

- details as wall 7, but design shear less \Rightarrow OK.

Stress & shear OK

ALAN REAY CONSULTANTS LIMITED

147 KILMORE ST
BOX 25-028, VICTORIA ST
CHRISTCHURCH 1

Telephone (03) 660-434
Fax No. (03) 793-981

FAXED

FACSIMILE TRANSMISSION

File 3602.

DATE: 10/10/91
TO: CSD Construction
ATTENTION: JIM FRY
CITY: CHCH
RECEIVERS FAX NO: 384 2817
FROM: GEOFF BLAIR
MESSAGE: 249 MADKIS ST

- Attached are our updated details as discussed.
- Contact Barry O'Neil at Obs re access for lift.

PLEASE CONTACT IMMEDIATELY IF 4 PAGES (INCLUDING THIS) ARE NOT RECEIVED

CONSTRUCTION DETAILS

4

249 MADRAS STREET -
LOCATION PLAN


5

PAGE	CD1
SECT	WALL TIES
FILE	3608
DATE	FEB 1990

C

NOTE:

- Remove ceiling panels and grid as necessary for installation. Reinstall on completion.
- Protect walls, carpet and lift as necessary.
- All materials & workmanship to comply with NZS 900
- All steelwork to be primed to a minimum thickness of 0.12 mm



stair well



D

Angle bracket
refer CD2.lift
shaftAngle bracket
refer CD3


CONSTRUCTION DETAILS

WALL TIE TO SLAB. GRID LINES D, 4/5
LEVELS 4-6.

PAGE	CD 2.
SECT	WALL TIES
FILE	3608
DATE	FEB 1990



PAGE	CD3
SECT	WALL TIES
FILE	3608
DATE	10/10/91



ALAN REAY CONSULTANTS LIMITED

147 KILMORE ST
BOX 25-028, VICTORIA ST
CHRISTCHURCH 1
Telephone (03) 660-434
Fax No. (03) 793-981

FILE 3608

11 October 1991

Mr M. Rogers
Ministry of Transport
Marine and Industrial Section
Private Bag
CHRISTCHURCH

Dear Sir

RE: LIFT SHAFT - 249 MADRAS STREET

As discussed with you yesterday, we confirm that we wish to install a structural steel angle in the lift shaft at levels 6, 5, and 4, as shown on the attached sketches 3608/CD1, 2, 3. The angle is a structural tie only, and is not supporting any additional services.

We understand that this detail is acceptable to you, and that the work may proceed.

Please contact the writer if you have any further queries.

Yours faithfully



G.N. Banks

Encl:

CONSTRUCTION DETAILS

4

249 MADRAS STREET -
LOCATION PLAN

5

PAGE	CD1
SECT	WALL TIES
FILE	3608
DATE	FEB 1990

C


NOTE:

- Remove ceiling panels and grid as necessary for installation. Reinstall on completion.
- Protect walls, carpet and lift as necessary.
- All materials & workmanship to comply with NZS 1900
- All steelwork to be primed to a minimum thickness of 0.12 mm

stair well

D

Angle bracket
refer CD2.lift
shaftAngle bracket
refer CD3



CD2

Cut back flange
to 80mm

*LS,4

*LS,4

*L4

*L4

*LS,4

*LS,4

*L4


7-26 dia holes for
7-M24 chemset - L6
5-M24 chemset - LS
4-M24 chemset - L4

12x 152x 152x 10 ms angle
2.690 long
10-22 dia holes for
10-M20 chemset - L6
8-M20 chemset - LS
6-M20 chemset - L4
(omit bolts noted *)

CONSTRUCTION DETAILS

WALL TIE TO SLAB.
GRID LINES D/E, 4/5.
LEVELS 4-6

PAGE	CD3
SECT	WALL TIES
FILE	3608
DATE	10/10/91



MARINE & INDUSTRIAL



S A F E T Y
I N S P E C T I O N
S E R V I C E S

Ngā Ratonga Ārai
Mate Ahumahi,
T a i m o a n a



Our Ref : 41/3/1

Your Ref : 3608

18 October 1991.

Alan Reay Consultants Ltd
P.O. Box 25-028
Victoria Street
Christchurch

Attention:- G. N. Banks

Dear Sir

LIFT SHAFT - 249 MADRAS STREET

Thank you for your letter of 11 October
concerning the above lift shaft.

I confirm that the details as shown on
sketches 3608/CD1, 2, and 3 are acceptable.

Yours faithfully

R. M. Rodgers
For Southern Operations Manager

A Service of the
Maritime Transport Division



Ministry of Transport
Te Manatū Waka

151-153 KILMORE ST
PRIVATE BAG
CHRISTCHURCH
NEW ZEALAND
TELEPHONE (03) 635-635
FACSIMILE (03) 665-748

FILE	3608
DATE	21/10/91
AMR	

**C.B.D.
CONSTRUCTION
LIMITED**

P.O. Box 10-318, Christchurch. Telephone (03) 842-455, Fax (03) 842-817

FILE	3608
DATE	15.10.91
AMR	

FAX FROM: GRANT BLACKMORE

FOR: JEFF BANKS

OF: ALAN REAY CONSULTANTS LIMITED

FAX NUMBER: 793 - 981

DESTINATION: CHRISTCHURCH

NO. OF PAGES (INCLUDING THIS HEADER): 2

PLEASE PHONE 842-455 IF THE PAGES ARE NOT WELL RECEIVED.

MESSAGE:



**CBD
CONSTRUCTION
LIMITED**

P.O. Box 10-318, Christchurch. Telephone (03) 384-2455, Fax (03) 384-2817

15 October 1991

Alan Reay Consultants Limited
P O Box 25-028
CHRISTCHURCH

Dear Sir

RE: 249 MADRAS STREET

Our quotation to supply and fix angle brackets as per details including remedial to floors broken out for investigation, \$4,633.50 (FOUR THOUSAND SIX HUNDRED AND THIRTY-THREE DOLLARS AND FIFTY CENTS ONLY) Plus G.S.T.

Yours faithfully

G.M Blackmore
QUANTITY SURVEYOR